

IMPROVEMENTS QUANTITIES

Project Name: Adams Avenue Roadway – Concrete Pan Improvements

Quantities stated in the bid tabulation below are estimated quantities only and it is understood the actual quantities in the field may vary from those estimated. Actual quantities will be measured in the field, unless specified otherwise in the bid item descriptions. Work required in this section includes all expenses to complete the individual bid items per the plans and specifications. Contractor shall provide unit bid cost for each item as follows:

BASE BID					
ITEM	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL COST
1	Concrete Valley Pan (6' Wide)	2148	SF		
2	Concrete Valley Pan (8' Wide)	640	SF		
3	Remove and Replace Asphalt Drives with Concrete	140	SF		

DESCRIPTIONS OF BASE BID ITEMS

Project Name: Adams Avenue Roadway – Concrete Pan Improvements

The following bid items must be bid and paid as outlined. Unit bid prices, as quoted in the bid schedule, shall constitute full compensation for materials, labor, equipment, rentals, permits, overhead, profit, incidentals, risk, loss, damage, and all other items of work and expense required for the complete construction of each pay item per the plans and specifications. Any items or like item not specifically mentioned as a bid item is considered incidental to the project and all costs associated with these items must be included in the bid items listed. These descriptions are to be used as a guide only for the bidder and reference to the plans and specifications should be made for the complete requirements.

BID ITEM 1 – Concrete Valley Pan (6' Wide)

This item is for the complete cost for the installation of concrete valley pans. The unit price shall include, but is not limited to, the cost of subgrade preparation, compaction, expansion joint material, rebar, dowels, and placement and finishing of concrete as shown in the plans.

BID ITEM 2 – Concrete Valley Pan (8' Wide)

This item is for the complete cost for the installation of concrete valley pans. The unit price shall include, but is not limited to, the cost of subgrade preparation, compaction, expansion joint material, rebar, dowels, and placement and finishing of concrete as shown in the plans.

BID ITEM 3 – Remove and Replace Asphalt Drives with Concrete

This item is for the complete cost for the saw cutting and removal of existing asphalt driveways and the installation of concrete to tie the remaining asphalt driveways into the new 6' concrete valley pan. The unit price shall include, but is not limited to, the cost of saw cutting and removal of existing asphalt, subgrade preparation, compaction, expansion joint material, rebar, dowels, and placement and finishing of concrete as shown in the plans.